BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/OW/WORK_INDENT9187/CALL-2

APPROVED SCHEDULE - B

Tender Notification No: No.EE/BTP/BBMP/E-PMT/16/2013-14, Date: 06.12.2013

Providing Cement Pipe 1mtr Dia to Ganesh Layout Park in Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of MADHIRAJU CHALAPATHI RAJU	
				In Figures	In Words
1	50	1056 - Hire Charges of Hydralic Excavator 1 Cum bucket including Operator and Fuel etc complete as per specifications and directions of engineer in charge of the work	Hr	1008.0	Rupees One Thousand Eight Only
2	92	KSRRB M2900-2.1: Laying reinforced cement concrete pipe NP4 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications, A.1000 mm dia,etc complete as per specifications and directions of engineer in charge of the work	M	10025.0	Rupees Ten Thousand Twenty Five Only
3	4	1087 - Hire Charges of Crane charges including Operator and Fuel etc complete as per specifications and directions of engineer in charge of the work	Day	3200.0	Rupees Three Thousand Two Hundred Only
4	1.6	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4283.5	Rupees Four Thousand Two Hundred Eighty Three and Fifty Paise Only
5	1.6	Providing and laying in position plain cement concrete of mix M15 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4779.0	Rupees Four Thousand Seven Hundred Seventy Nine Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92